

	Skilled Worker																
	Helper																
	Equipment	eqpt	days														
	Cutting Machine/Cut-off Wheel	1.00	6.00														
	Sub-Total																
VI	PAINTING WORKS	43.48	sq.m.														
	Materials:																
	<i>Concrete Walls, Columns, and Beams</i>																
	Exterior																
	Concrete Neutralizer	2.00	liter														
	Acrylic Concrete Primer and Sealer	3.00	gal														
	Elastomeric Putty (full)	5.00	gal														
	Acrylic Odourless Elastomeric Paint	5.00	gal														
	Miscellaneous																
	7" Roller paint with pan	8.00	sets														
	Paint Brush, 4"	2.00	pcs														
	Paint Brush, 2"	2.00	pcs														
	Paint Brush, 1"	2.00	pcs														
	Sandpaper, #100	25.00	ft														
	Labor:	man	days														
	Project Engineer																
	Construction Foreman																
	Skilled Worker / Painter																
	Helper																
	Sub-Total																
VII	ROOFING WORKS																
	(a) Steel Truss	1.00	lot														
	Materials:																
	2" x 2" x 2.5mm Angle bar	21.00	pcs.														
	2" x 2" x 5mm Angle bar	13.00	pcs.														
	2" G.I. Pipe Sch. 40	51.00	pcs.														
	10mmØ round bar, Sagrod	10.00	pcs.														
	100mm x 50mm x 1.5mm C-Purlins	78.00	pcs.														
	20mmØ x 150mm Anchor Bolt with Knot and Washer	79.00	pcs.														
	20mmØ x 150mm Anchor Bolt with Knot and Washer (Double Ended)	6.00	pcs.														
	200mm x 650mm x 10mm Steel Plate	4.00	pcs														
	320mm x 75mm x 10mm Steel Plate	4.00	pcs														
	150mm x 200mm x 10mm Steel Plate (L-Shape)	4.00	pcs														
	50mm x 200mm x 10mm Steel Plate (L-Shape)	2.00	pcs														
	Welding Rod,5kgs/box	20.00	boxes														
	Cutting Disc 4"	75.00	pcs														
	Cut-off Wheel 14"	15.00	pcs														
	Red Oxide Primer	19.00	gal.														
	Quick Drying Enamel	19.00	gal.														
	Paint Thinner	36.00	bots														
	Paint Brush 4"	15.00	pcs														
	Paint Brush 2"	15.00	pcs.														
	Labor:	man	days														
	Project Engineer																
	Construction Foreman																
	Skilled Worker																
	Helper																
	Equipment	eqpt	days														
	Welding Machine	2.00	10.00														
	Cutting Machine	1.00	10.00														
	Sub-Total																
	(b) Roofing Sheet	250.90	sq.m.														
	Materials:																
	0.5mm thk Pre Painted Pre Fabricated 13.1m long G.I. Sheet, Rib Type, Pre-bend (R=50.5m)	22.00	pcs														
	0.5mm thk x 3ft x 12ft G.I. Sheet, Rib Type	16.00	pcs														
	0.5mm thk x 4ft x 8ft Perforated Metal Sheet (SS304)	5.00	pcs														
	2 1/2" Teckscrew, Metal	2,450.00	pcs														
	10mm thk Double Sided Insulation, (50m/roll)	7.00	rolls														
	1"x 1"x 4ft Galvanized Screen, (30m/roll)	12.00	rolls														

211.16
211.16

227.16
216.16

	#16 G.I. Tiewire	10.00	kgs															
	Weatherproofing Sealant, 1.0kg	5.00	kgs															
	0.5mm thk G.I. Fascia, 2'x8'	8.00	pcs															
	0.5mm thk x 12" Spanish Gutter, 8'	8.00	pcs															
	Labor:	man	days															
	Project Engineer																	
	Construction Foreman																	
	Skilled Worker / Tinsmith																	
	Helper																	
	Equipment	eqpt	days															
	Electric Hand Drill	1.00	7.00															
	Sub-Total																	
VIII	ELECTRICAL WORKS	1.00	lot															
	Materials:																	
	3.5mm ² THHN Copper Wire	1.00	box															
	19" Ø High Bay Polycarbonate Reflector with Polycarbonate Cover	8.00	pcs															
	Low Bay Reflector Bracket with E27 Receptacle	8.00	pcs															
	20 watts LED Bulb Day Light E27	8.00	pcs.															
	Junction Box with cover, GI Gauge 24	8.00	sets															
	1/2" Ø Electrical Metallic Tubing	20.00	pcs.															
	1/2" Ø lock nut and bushing	17.00	pcs															
	Electrical Tape Big	2.00	rolls															
	screws, bolts, hanger and elbows	1.00	lot															
	Labor:																	
	Installation Cost	1.00	lot															
	Sub-Total																	
IX	PLUMBING WORKS	1.00	lot															
	Materials:																	
	3" Ø uPVC Rainwater Pipe, series 1000, 3m	14.00	pcs															
	3" Ø uPVC Sanitary Elbow 90°	14.00	pcs															
	3" Ø uPVC Sanitary Tee	2.00	pcs															
	3" Ø uPVC Sanitary Coupling	8.00	pcs															
	3" Ø Stainless Steel Strainer	6.00	pcs															
	Solvent Cement (200cc/can)	22.00	cans															
	Labor:	man	days															
	Project Engineer																	
	Construction Foreman																	
	Skilled Worker																	
	Helper																	
	Sub-Total																	
	GRAND TOTAL																	

Submitted by:

Name of the Representative of the Bidder: _____

Position: _____

Signature of the Bidder: _____

Date: _____