



Republic of the Philippines
Center for Health Development No.2
REGION II TRAUMA AND MEDICAL CENTER
Bayombong, Nueva Vizcaya

SCOPE OF WORKS

Project Title	SUPPLY OF LABOR, MATERIALS AND EQUIPMENT FOR THE INSTALLATION OF STREET LIGHT AT FIVE (5) BED NEGATIVE PRESSURE BUILDING
Location	REGION II TRAUMA AND MEDICAL CENTER
Source of Fund	BAYANIHAN 2
Appropriation	Php 738,062.52
Proposed Budget for the Contract	Php 738,062.52
Project Duration	30 Calendar Days
Project Type	
Mode of Implementation	By Contract
Project Description	Supply of Labor, Materials and Equipment for the Installation of Street Light at Five (5) Bed Negative Pressure Building
Equipment Requirements:	(a) Boom Truck (b) Grinder (c) Driller

Scope of Work

Item	Description of Work	Unit	Qty	Specification
I.	GENERAL REQUIREMENTS <ul style="list-style-type: none"> Mobilization/Demobilization Temporary/Facilities, Water and Electric Consumption, Safety and Health Program Project Billboard Furnishing of Materials, Labor, and Equipment 	lot	1.00	<ul style="list-style-type: none"> Mobilization/demobilization of equipment, material, manpower and temporary facilities to the site including clearing of all waste or debris generated during the entire construction duration. Construction of Site Office and other temporary facilities. Observe the use of good source of potable water, and source of electricity for the entire duration of the project. The contractor shall, at his own expense, furnish his workers with protective equipment for eyes, face, hands and feet, lifeline, safety belt/harness, protective shields and barriers whenever necessary by reason of the hazardous work process or environment, chemical or radiological or other mechanical irritants of hazards capable of causing injury or impairment in the function of any part of the body through absorption, inhalation or physical agent All Personal Protective Equipment and Devices shall be in accordance with the requirement of the Occupational Safety and Health Standards (OSHS) and should pass the test conducted and/or standards sets by the Occupational Safety and Health Center (OSHC). Billboard shall be installed prior to all items programmed in the project. Contents of billboard shall be as indicated under COA Circular No. 2013-004 Billboard shall be installed in a safe & visible location near or within the starting point of the project or as directed by the R2TMC Engineer-in-charge of the project. The construction shall conform to all the requirements of the National Building Code, Department of Health, as well as the local rules and regulations of the Municipality of Bayombong, Nueva Vizcaya.
II	ELECTRICAL WORKS General <ul style="list-style-type: none"> Furnishing of Materials, and Labor 	lot	1.00	<ul style="list-style-type: none"> All works shall be done under the direct supervision of an Electrical Engineer and in strict accordance with these specifications and of the methods as prescribed by the latest edition of the Philippine Electrical Code. All items not specifically mentioned in the specifications as noted on the drawing but which are obviously necessary to make a complete working installation shall be included. All materials shall be brand new and shall be of the approved type meeting all the requirements of the Philippine Electrical Code and bearing the Philippine Standard Agency (PSA) mark unless specified or indicated otherwise. All materials to be used shall conform to the Bureau of Product Standard (BPS) Specifications. Upon completion of the electrical construction work, the contractor shall provide all test equipment and personnel and to submit written copies of all test results. <p>General Note:</p> <ul style="list-style-type: none"> Any discrepancies within the issued drawings/plans and specifications, the actual site condition and actual construction shall be conferred with the R2TMC Engineers and no execution of work shall be done without their consent and final approval. All materials and workmanship shall conform to the latest applicable standards or specifications. All works shall conform to the best practice prevailing in the various trades. All construction and workmanship shall be subject to inspection, examination and testing by the R2TMC Engineer-in-charge of the project. The R2TMC Engineer-in-charge of the project shall have the right to reject defective materials and workmanship or require its correction.

Submitted by:

Name of the Representative of the Bidder: _____

Position: _____

Signature of the Bidder: _____

Date: _____